Australasian HFG Standard Components

Milestone: Default Room Data Sheets

Department Standard Components Room Tag: 1730

Room Name Catheter Lab Control/ Reporting Room Room Code: CLCRT

Area 14.0 M2
No of Rooms 1

Subtotal of Area 14.0 M2

Hours of Operation Available 24 Hours

Occupancy Up to 3 staff

Also covers these Rooms

Description/ Special Requirements Room adjacent to Catheter Lab Procedure Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control/ Reporting room may serve two procedure rooms.

Acoustics: Acoustic privacy is required

Additional Design Considerations:

- Radiation shielding as advised by Radiation Consultant
- Cable ducts from Angiography Procedure Room and Computer/Equipment room may be required

Amendment

14.03.05, - First Draft

20.04.05, - BOB User review, area modified

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high		
9004	Doors	Solid Core/ Glass	Paint	Single leaf, observation panel		910mm clear opening
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
7025	Observation	Lead glass	Clear	Internal window		to procedure room
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection		
1050	Bench: laminate	Furniture/ Fitting	1	1	at 900H		
1950	Chair: ergonomic, high	Furniture/ Fitting	3	3			
3400 Coathook		Metalwork	1	2			
17252	Pedestal drawer unit: mobile, 840mmH	Furniture/ Fitting	3	1	under bench		
17360	Pinboard: fabric covered	Furniture/ Fitting	1	2	over bench		
20000	Shelving unit: adjustable	Furniture/ Fitting	1	2	for books, manuals, over bench		
24400	Whiteboard	Furniture/ Fitting	2		optional		

Australasian HFG Standard Components

Milestone: Default Room Data Sheets

Department Room Name

Standard Components

Catheter Lab Control/ Reporting Room

Room Tag: 1730
Room Code: CLCRT

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Тар	Dns	Gas	Selection
11400	Computer: PC & monitor	3	1	yes	yes							flat screen
62150	IMG: console, control	1	1	yes	yes							Cath lab control monitors
35950	Monitor	3	2	yes	opt							patient
41100	Printer: networked	3	1	yes	yes							
54510	Telephone: handset, standard	3	2		yes							on bench

Services

ID	Description	Service Category	Qty	Remarks
1040	Intercom	Communications	1	with handsfree microphone to Angio room
1006	Voice / Data outlet: double	Communications	6	3 outlets under bench for telephone
5000	Airconditioning	HVAC		
6000	General fluorescent	Lighting		
6055	Special: task light, built in	Lighting		under O/H shelving
9001	GPO: Double	Power	9	
9060	GPO: Special: for equipment	Power	1	Cath lab console equipment