Australasian Standard Project
Room Data Sheets

Department	Standard Components	**Room Tag:**	2430
Room Name	Film Processing, Viewing and Reporting	**Room Code:**	FPVR

Area	16.0 M2
No of Rooms	1
Subtotal of Area	16.0 M2
Hours of Operation	8am to 8pm, daily
Occupancy	Up to 4
Also covers these Rooms	
Description/ Special Requirements	A room located within the Medical Imaging Unit to accommodate the film processing equipment along with a workstation area for viewing, and reporting of images. Acoustics: Sound attenuation level - Medium; acoustic privacy required.
Amendment	26.05.05, - First Draft

Room Fabric and outline specifications

ID	Fabric	Material	Finish	Specification	Selection	Remarks
5060	Ceiling	Acoustic	Prefinished	Drop-in tiles, 600x1200		
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high		
9004	Doors	Solid Core/ glass	Paint	Single leaf, observation panel		910mm clear opening, glazing optional
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved		
7010	Observation	Glass	Clear	Through door/s		
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH		
3000	Wall finish	Paint	Acrylic, washable			
3060	Wall finish	Vinyl	Prefinished	Splashback		above sink, tiles also acceptable

Fittings and Furniture (FF)

ID	Description	Category	Group	Qty	Selection
1050	Bench: laminate	Furniture/ Fitting	1	1	with inset sink
1120	Bench: workstation	Furniture/ Fitting	1	1	
2100	Chair: ergonomic, office	Furniture/ Fitting	3	2	
3350	Clock: battery operated	Furniture/ Fitting	3	1	
21290	Cupboard: steel	Furniture/ Fitting	3	1	chemical storage
4410	Cupboard: under bench	Furniture/ Fitting	1	1	adjustable shelves
4460	Cupboard: wall mounted	Furniture/ Fitting	1	1	over sink bench, adjustable shelves
6154	Dispenser: paper/ hand towel	Furniture/ Fitting	2	1	to sink
6156	Dispenser: soap	Furniture/ Fitting	2	1	to sink
17360	Pinboard: fabric covered	Furniture/ Fitting	1	1	above bench
20000	Shelving unit: adjustable	Furniture/ Fitting	1	1	over workstation bench
24100	Waste bin: paper, 20 Litre	Furniture/ Fitting	3	1	

This document is for advisory purpose only

Department	Standard Components	**Room Tag:**	**2430**
Room Name	Film Processing, Viewing and Reporting	**Room Code:**	**FPVR**

Fixtures, Equipment and associated Services (FE)

ID	Description	Group	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Selection
11415	Computer: PACS	3	2	yes	yes	___	___	___	___	___	___	for computerised images
65100	IMG: processor, daylight	3	1	yes	___	yes	___	___	yes	yes	___	
65900	IMG: silver recovery unit	3	1	___	___	___	___	___	___	yes	___	
41100	Printer: networked	3	1	yes	yes	___	___	___	___	___	___	
49115	Sink: 600x450x450D	1	1	___	___	yes	opt	opt	yes	yes	___	hot water, lab sink
54510	Telephone: handset, standard	3	3	___	yes	___	___	___	___	___	___	
69210	Xray viewer: multiscreen	1	1	yes	___	___	___	___	___	___	___	optional

Services

ID	Description	Service Category	Qty	Remarks
1006	Voice / Data outlet: double	Communications	4	2 outlets on workstations for telephone
1006	Voice / Data outlet: double	Communications	1	printer
5000	Airconditioning	HVAC		
6005	Dimmable	Lighting		for image viewing
6000	General fluorescent	Lighting		
6055	Special: task light, built in	Lighting	1	under O/H shleving
9001	GPO: Double	Power	5	2 per workstation + 1- printer
9060	Special: for equipment	Power	2	Processor, XRV

Australasian **HFG**

Provided by HPI for :

HCAMC

Issue No: 1

Issue Date: 4 Aug 2005

Print Date: 4 Aug 2005

Page 2 of 2

This document is for advisory purpose only