

# Australasian Standard Project

## Room Data Sheets

|  |   |                        |
|--|---|------------------------|
| <b>Department</b>                        | <b>Standard Components</b>  | <b>Room Tag: 3110</b>  |
| <b>Room Name</b>                         | <b>Neonatal Bay - General Care</b>  | <b>Room Code: NBGC</b> |
| <b>Area</b>                              | 5.0 M2  |                        |
| <b>No of Rooms</b>                       | 1   |                        |
| <b>Subtotal of Area</b>                  |   |                        |
| <b>Hours of Operation</b>                | 24 Hours  |                        |
| <b>Occupancy</b>                         | 1 baby; 1-2 staff   |                        |
| <b>Also covers these Rooms</b>           |   |                        |
| <b>Description/ Special Requirements</b> | <p>A single bay for the care of well babies away from their mother's bed area which may include treatments such as phototherapy. A staff handwash basin should be provided for each four Neonatal Bays - General Care. An external outlook is required.</p> <p>Acoustics: Sound attenuation level - high; Acoustic privacy is required to perimeter walls</p> <p>Body Protected electrical area</p> |                        |
| <b>Amendment</b>                         | 24.01.05, - First Draft   |                        |

### Room Fabric and outline specifications

| ID   | Fabric          | Material     | Finish                  | Specification                | Selection | Remarks            |
|------|-----------------|--------------|-------------------------|------------------------------|-----------|--------------------|
| 5010 | Ceiling         | Plasterboard | Paint, washable         | Flush set, suspended         |           |                    |
| 6010 | Cornice         | Plasterboard | Paint                   | 90mm to match ceiling finish |           |                    |
| 1000 | Floor finish    | Vinyl        | Standard slip resistant | Seamless, coved              |           |                    |
| 2000 | Skirting        | Vinyl        | Prefinished             | Floor vinyl coved, 150 mmH   |           |                    |
| 3000 | Wall finish     | Paint        | Acrylic, washable       |                              |           |                    |
| 4020 | Wall protection | Composite    | Prefinished PVC         | Crash rail at 900 AFFL       |           | Equal to 'Acrovyn' |
| 7001 | Windows         |              |                         |                              |           | Essential          |

### Fittings and Furniture (FF)

| ID    | Description             | Category           | Group | Qty | Selection                       |
|-------|-------------------------|--------------------|-------|-----|---------------------------------|
| 150   | Air flowmeter           | Furniture/ Fitting | 3     | 1   | shared between 4 bays           |
| 480   | Bassinet                | Furniture/ Fitting | 3     | 1   |                                 |
| 1465  | Bracket: suction bottle | Furniture/ Fitting | 2     | 1   | shared between 4 bays           |
| 16250 | Oxygen flowmeter        | Furniture/ Fitting | 3     | 1   | optional, shared between 4 bays |
| 22000 | Suction bottle          | Furniture/ Fitting | 3     | 1   | shared between 4 bays           |

### Fixtures, Equipment and associated Services (FE)

#### Services

| ID   | Description     | Service Category | Qty | Remarks |
|------|-----------------|------------------|-----|---------|
| 5000 | Airconditioning | HVAC             |     |         |

**Australasian Standard Project**  
**Room Data Sheets**

**Department** | **Standard Components**  
**Room Name** | **Neonatal Bay - General Care**

**Room Tag: 3110**  
**Room Code: NBGC**

| ID    | Description               | Service Category | Qty | Remarks                  |
|-------|---------------------------|------------------|-----|--------------------------|
| 6005  | Dimmable                  | Lighting         |     | variable lighting level  |
| 6001  | General: colour corrected | Lighting         |     |                          |
| 7020  | Medical Air (MA)          | Medical Gases    | 1   | shared between 4 bays    |
| 7000  | Oxygen (O2)               | Medical Gases    | 1   | shared between 4 bays    |
| 7040  | Suction                   | Medical Gases    | 1   | shared between 4 bays    |
| 8080  | Emergency call            | Nurse Call       | 1   | shared between 4 bays    |
| 8010  | Staff/ Nurse assist call  | Nurse Call       | 1   | shared between 4 bays    |
| 9040  | Body protected            | Power            |     |                          |
| 9015  | GPO: Cleaner              | Power            | 1   | to serve a group of bays |
| 9000  | GPO: Single               | Power            | 2   | shared between 2 bays    |
| 11000 | Wall panel                | Services Panels  | 1   |                          |