

Room Name	Catheter Lab Control/ Reporting Room	Room Number: CLCRT
Last modified	01/03/2016	
Briefed Area	14.00	
Remarks		
Occupancy	Up to 3 staff	
Hours of Operation	<input checked="" type="checkbox"/> Available 24 Hours	
Acoustics	Acoustic privacy is required	
Description / Special Requirements	Room adjacent to Catheter Lab Procedure Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control/ Reporting room may serve two procedure rooms. Acoustics: Acoustic privacy is required. Additional Design Considerations: - Radiation shielding as advised by Radiation Consultant - Cable ducts from Angiography Procedure Room and Computer/Equipment room may be required	

Room Fabrics

AusHFG code	Description	Material	Finish	Specification	Comments
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved	
3000	Wall finish	Paint	Acrylic, washable		
5060	Ceiling - Acoustic	Acoustic	Prefinished	Drop-in tiles, 600x1200	
8000	Door protection	Vinyl	Prefinished	Kickplate, 300mm high	
9004	Door - 1100mm	Solid Core/ Glass	Paint	Single leaf, observation panel	910mm clear opening
7025	Observation	Lead glass	Clear	Internal window	to procedure room
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle	
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH	

Fittings and Furniture

AusHFG code	Description	Group	Qty	Comments
FF-1050	Bench - laminate	1	3	at 900H
FF-16840	Partitions - laminate	1	2	as required
FF-17250	Pedestal drawer unit - mobile, 660mmH	3	1	
FF-17360	Pinboard - fabric covered	1	3	over bench
FF-1950	Chair - ergonomic, high	3	3	
FF-20000	Shelving unit - adjustable	1	6	for books, manuals, over bench
FF-3400	Coathook	1	2	
FF-24405	Whiteboard - magnetic	2	1	optional

Fixtures, Equipment and associated Services

AusHFG code	Description	Grp	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Comments
FE-11400	Computer - PC & monitor	3	1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	flat screen
FE-35950	Monitor	3	1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	patient
FE-41100	Printer - networked	3	1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

Room Name | Catheter Lab Control/ Reporting Room

Room Number: CLCRT

AusHFG code	Description	Grp	Qty	Ele	Data	CdW	HtW	WmW	Tap	Dns	Gas	Comments
FE-54510	Telephone - handset, standard	3	2	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	on bench
FE-62150	IMG - console, control	1	1	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Cath lab control monitors

Service Requirements

AusHFG code	Description	Comments
S-5000	Airconditioning	
S-6000	General fluorescent	
S-6055	Special: task light, built in	under O/H cupboards

Services

AusHFG code	Description	Group	Qty	Comments
S-9001	GPO: Double	1	9	
S-9060	GPO: Special: for equipment	1	1	TV, ceiling
S-1006	Voice / Data outlet: double	1	6	1 outlet for telephone
S-1040	Intercom	1	1	optional
S-5000	Airconditioning	1	1	
S-6000	General fluorescent	1	1	
S-6200	Light switches	1	2	
S-6055	Special: task light, built in	1	4	under O/H cupboards