

## **Standard Components - Room Data Sheet**

Room Name Staff Station, 20m2 Room Number: SSTN-20

Last modified 01/03/2016

Briefed Area Remarks 20.00

Acoustics

ics Sound attenuation level medium, Acoustic privacy is required.

Description or Special Requirements

The Staff Station is the administrative base for a Unit in which it is located, and enquiry point for patients and visitors. It provides for the co-ordination of patient care, observation, writing up of clinical notes, entering data into computers and making and receiving telephone calls. The Staff Station may also accommodate a Unit Receptionist/ Clerk. The floor area may vary according to the Health Planning Unit in which it is located, activity level, number of full and part-time staff, the Operational Model and the building layout. A 20m2 Staff Station wll predominatantly be used in Critical Care Units such as ICU, CCU, NICU, PICU etc.Acoustics: Sound attenuation level - Medium; acoustic privacy required. Special Design Requirements: - Staff Station should have a set down area for disabled access - Lockable counter height doors may be provided for additional security if required. - If doors are required, access for disabled staff may require consideration

#### **Room Fabrics**

AusHFG code	Description	Material	Finish	Specification	Comments	
1000	Floor finish	Vinyl	Standard slip resistant	Seamless, coved	Default = vinyl; carpet also acceptable	
3000	Wall finish	Paint	Acrylic, washable			
4010	Wall protection	Composite	Prefinished PVC	Combined rail & crash bar at 900 AFFL	to front of desk, optional	
5007	Ceiling - Plasterboard	Plasterboard	Paint	Bulkhead	optional	
5060	Ceiling - Acoustic	Acoustic	Prefinished	Drop-in tiles, 600x1200		
9002	Door - 910mm	Solid Core/ Glass	Paint	Single leaf, half glazed	910mm clear opening, optional to adjoining Office-Clinical	
9050	Door - 910mm	Laminate	Prefinished	Single leaf, counter height	910mm clear opening, lockable, optional for security	
6030	Cornice	Aluminium	Powdercoat	24mm shadow angle		
2000	Skirting	Vinyl	Prefinished	Floor vinyl coved, 150 mmH	Default = coved vinyl; vinyl featheredge skirting over carpet	

#### Fittings and Furniture

AusHFG code	Description	Group	Qty	Comments
FF-11465	Keyboard shelf - drop down	1	4	optional
FF-17250	Pedestal drawer unit - mobile, 660mmH	3	4	
FF-17255	Pedestal filing unit - mobile, 660mmH	3	4	under bench, lockable
FF-17360	Pinboard - fabric covered	1	3	to upstand of staff station
FF-2100	Chair - ergonomic, office	3	4	
FF-21250	Staff station - laminate/ timber	1	1	
FF-4230	Counter top	1	1	resinate or laminate, to staff station
FF-5824	Waste bin - general	3	1	

Fixtures, Equipment and associated Services







# **Standard Components - Room Data Sheet**

Room Name Staff Station, 20m2 Room Number: SSTN-20

AusHFG code	Description	Grp	Qty	Ele	Data	CdW	HtW	WmW	Тар	Dns	Gas	Comments
FE-11400	Computer - PC & monitor	3	4	<b>V</b>	<b>V</b>							
FE-54510	Telephone - handset, standard	3	2		V							
FE-68700	Xray viewer - 2 screen	1	1	<b>V</b>								recessed
FE-8830	Monitor - central station, ICU	3	1	V	V							as required

# **Service Requirements**

AusHFG code	Description	Comments		
S-5000	Airconditioning			
S-6000	General fluorescent			
S-6030	Special: downlights	over bed/ trolley		
S-6055	Special: task light, built in	under O/H cupboards		

### **Services**

AusHFG code	Description	Group	Qty	Comments
S-9001	GPO: Double	1	8	
S-9060	GPO: Special: for equipment	1	1	TV, ceiling
S-1006	Voice / Data outlet: double	1	4	1 outlet for telephone
S-1120	Monitor connection facilities and cabling	1	1	optional
S-5000	Airconditioning	1	1	
S-5070	Temperature control	1	1	control panel, optional
S-1416	Light Control Panel		1	Imported 150916
S-6000	General fluorescent	1	1	
S-6200	Light switches	1	3	
S-6030	Special: downlights	1	1	over bed/ trolley
S-6055	Special: task light, built in	1	4	under O/H cupboards
S-8040	Annunciator	1	1	
S-10005	Duress alarm	1	1	
S-7050	Gas Alarm Panel	1	1	



