Room Name	Audiology Control Room	Room Number AUD-CR

Revision	1
Issue Date	26.04.2021

BRIEFING

Briefed Area	9.00 m^2
Hours of Operation	8am to 6pm, daily
Occupancy	1 staff
Acoustics	Acoustic privacy is required
Remarks	
Description / Special Requirements	The Audiology Control Room may be provided adjacent to the Audiology Testing Room to support the administering of tests that require discrete observation, result verification by a second clinician and/or remote control of equipment. The room will require a workspace and visibility of the Testing Room via an observation window.

Additional Consideration:

- The floor of the Control Room should be flush with the floor of the Treatment Room and the adjacent corridor for access by patients in wheelchairs.
- Portable equipment may be shared between the Control Room and the Treatment Room.

SERVICES

Electrical	BODY PROTECTED	☑	CARDIAC PROTECTED ☐
HVAC	AIRCONDITIONING	☑	AIRCONDITIONING: hepa filtered ☐
	AIRCONDITIONING: positive pressure ☐		AIRCONDITIONING: negative pressure ☐
	EXHAUST: room exhaust ☐		VENTILATION ☐
Lighting	LIGHTING: colour corrected ☐		LIGHTING: dimmable ☐
	LIGHTING: downlights ☐		LIGHTING: downlights, dimmable ☑
	LIGHTING: fluorescent/LED, downlights ☐		LIGHTING: fluorescent/LED, flush with ceiling, tamper proof ☐
	LIGHTING: fluorescent/LED, general ☐		LIGHTING: indirect ☐
Security / Nurse Call	NURSE CALL SYSTEM ☐		

Room Fabrics

AusHFG code	Description	Comment
CLTI-002	CEILING: acoustic, drop-in tiles, 600 x 1200	
CLCN-009	CORNICE: wall trim fixing	
DWGL-005	DOOR: 910mm c/o, single leaf, observation panel, solid core/glass, paint	acoustic seals to suit testing requirements
DWPR-001	DOOR PROTECTION: kickplate, to 300 AFFL	
FLCP-006	FLOOR FINISH: carpet, carpet tiles, 90/10 wool/nylon	
FLSK-009	SKIRTING: vinyl, feather edged, 150H, prefinished	
WLWA-004	WALL FINISH: paint, acrylic, washable	

Fittings, Furniture and Equipment (FF&E) Items

AusHFG code	Description	Group	Qty	Comment
FQCW-016	BIN: waste, general, 20L	3	1	

Room Name	Audiology Control Room	Room Number AUD-CR

AusHFG code	Description	Group	Qty	Comment
MMAH-005	BOOTH: audiometric	3	1	one way window (non-reflective); acoustic seals to suit testing requirements
FQBS-018	CHAIR: office, ergonomic	3	1	
ITNE-007	COMPUTER: desktop, with display screen	3	1	optional
MMAH-036	CONSOLE: control, audiometric booth	3	1	optional, dependent on service requirements
MMAH-042	DEVICE: tympanometer	3	1	
FIDI-001	DISPENSER: alcohol based hand rub	2	1	
FIDI-014	DISPENSER: disposable glove	2	1	
FIDI-021	DISPENSER: mask	2	1	
FQSM-007	PEDESTAL: mobile, drawer unit, 660H	3	1	
ITNE-049	TELEPHONE: handset, desktop	3	1	
FQDW-031	WORKSTATION: straight, adj height, 1650W x 750D x 750H nom.	3	1	

Engineering Services

AusHFG code	Description	Group	Qty	Comment
ELGP-208	GPO: double, wall mounted	1	3	provision of emergency power to be determined based on service requirements
ELGP-110	GPO: single, wall mounted, cleaner	1	1	
ITIN-026	OUTLET: data, double RJ45, wall mounted	1	1	
ELPR-006	RCD: residual current device	1	1	
MMSP-032	SERVICES PANEL: instrument jack	1	1	optional
ELBO-012	SWITCH: light, dimmer	1	1	