Room Name	Catheter Lab Control/ Reporting Room	Room Number CLCRT

Revision	3
Issue Date	20.03.17

BRIEFING

Briefed Area	14.00 m^2
Hours of Operation	Available 24 Hours
Occupancy	Up to 3 staff
Acoustics	Acoustic privacy is required
Remarks	
Description / Special Requirements	Room adjacent to Catheter Lab Procedure Room/s with direct visibility to the patient for remote control of equipment, and review and reporting of procedure images. The Control/ Reporting room may serve two procedure rooms. Additional Design Considerations: Radiation shielding as advised by Radiation Consultant. Cable ducts from Angiography Procedure Room and Computer/Equipment room may be required.

SERVICES

General Requirements	BODY PROTECTED = No	CARDIAC PROTECTED = No
Air	AIRCONDITIONING = Yes	AIRCONDITIONING: hepa filtered = No
	AIRCONDITIONING: positive pressure = No	AIRCONDITIONING: negative pressure = No
	EXHAUST: room exhaust = No	VENTILATION = No
Lighting	LIGHTING: colour corrected = No	LIGHTING: dimmable = No
	LIGHTING: downlights = No	LIGHTING: downlights, dimmable = No
	LIGHTING: fluorescent, downlights = No	LIGHTING: fluorescent, flush with ceiling, tamper proof = No
	LIGHTING: fluorescent, general = Yes	LIGHTING: indirect = No
Nurse Call	NURSE CALL SYSTEM = No	

Room Fabrics

AusHFG code	Description	Comment
CLTI-002	CEILING: acoustic, drop-in tiles, 600 x 1200	
CLCN-002	CORNICE: aluminium, 24mm shadow angle, powdercoat	
DWGL-005	DOOR: 910mm c/o, single leaf, observation panel, solid core/glass, paint	any doors connecting directly to Catheter Lab Procedure room must include lead shielding
DWPR-003	DOOR PROTECTION: kickplate, to 300 AFFL, vinyl, prefinished	
FLVY-007	FLOOR FINISH: vinyl, seamless, coved, standard slip resistant	
DWOB-009	OBSERVATION: internal window, lead glass, clear	to procedure room
FLSK-010	SKIRTING: vinyl, floor vinyl coved, 150H, prefinished	
WLWA-004	WALL FINISH: paint, acrylic, washable	

Fittings, Furniture and Equipment (FF&E) Items

AusHFG code	Description	Group	Qty	Comment
FIJO-044	BENCH: special depth, open under	1	3	laminate finish, at 900H, 800/600D
FQBS-019	CHAIR: office, ergonomic, high	3	3	
ITNE-007	COMPUTER: desktop, with display screen	3	1	flat screen
MMMI-013	CONSOLE: control, examination control console, angiography single plane ceiling	1	1	Cath lab control monitors

Room Name	Catheter Lab Control/ Reporting Room	Room Number CLCRT

AusHFG code	Description	Group	Qty	Comment
FIJO-152	CUPBOARD: wall mount, shelf unit, adj shelves	1	6	for books, manuals, over bench
FIHR-026	HOOK: coat	1	2	
MMGE-073	MONITOR: vital signs, dual screen	3	1	patient
FIBM-013	NOTICEBOARD: fixed, fabric covered	1	3	over bench
WLPT-003	PARTITION: laminate	1	2	as required
FQSM-007	PEDESTAL: mobile, drawer unit, 660H	3	1	
ITNE-023	PRINTER: networked	3	1	
ITNE-049	TELEPHONE: handset, desktop	3	2	on bench
FIBM-019	WHITEBOARD: fixed, magnetic	2	1	optional

Engineering Services

AusHFG code	Description	Group	Qty	Comment
ELGP-208	GPO: double, wall mounted	1	9	
ELGP-106	GPO: single, special, for equipment	1	1	Cath lab console equipment
ITSE-029	INTERCOM: audio, wall mount	1	1	with handsfree microphone to Angio room
LIFX-008	LIGHT: task light, built in	1	4	under O/H shelving
ITIN-026	OUTLET: data, double RJ45, wall mounted	1	6	2 outlets under bench for telephone
ELBO-015	SWITCH: light, single	1	2	