

Room Name	Set-up Room	Room Number SETUP-8			
Revision	3				
Issue Date	20.03.17				
BRIEFING					
Briefed Area	8.00 m ²				
Hours of Operation	24 Hours				
Occupancy	1 - 2 intermittently				
Acoustics	·				
Remarks					
Description / Special Requirements	A room for storage and holding of sterile stock for use in the Operating Unit, and set-up of case trolleys for operating procedures. The Set-up area will be located with direct access to Operating Rooms and ready access from CSSU for receipt of sterile stock.				
SERVICES					
General Requirements	BODY PROTECTED = No	CARDIAC PROTECTED = No			
Air	AIRCONDITIONING = No	AIRCONDITIONING: hepa filtered = Yes			
	AIRCONDITIONING: positive pressure = Yes	AIRCONDITIONING: negative pressure = No			
	EXHAUST: room exhaust = No	VENTILATION = No			
Lighting	LIGHTING: colour corrected = No	LIGHTING: dimmable = No			
	LIGHTING: downlights = No	LIGHTING: downlights, dimmable = No			
	LIGHTING: fluorescent, downlights = No	LIGHTING: fluorescent, flush with ceiling, tamper proof = No			
	LIGHTING: fluorescent, general = Yes	LIGHTING: indirect = No			
Nurse Call	NURSE CALL SYSTEM = No				

Room Fabrics

AusHFG code	Description	Comment
CLFS-005	CEILING: plasterboard, flush set, suspended, paint, scrub resistant	
CLCN-002	CORNICE: aluminium, 24mm shadow angle, powdercoat	
DWGL-015	DOOR: 1050mm c/o, single leaf, observation panel, solid core/glass, paint	sliding panel on obs to doors to ORs
DWPR-006	DOOR PROTECTION: protection plate, to 900 AFFL, PVC, prefinished	
DWPR-010	DOOR PROTECTION: to door frame, PVC, prefinished	
FLVY-007	FLOOR FINISH: vinyl, seamless, coved, standard slip resistant	
FLSK-010	SKIRTING: vinyl, floor vinyl coved, 150H, prefinished	
WLWA-004	WALL FINISH: paint, acrylic, washable	
WLPR-012	WALL PROTECTION: corner guards, to 900 AFFL, prefinished PVC	Equal to Acrovyn, as required
WLPR-019	WALL PROTECTION: crash rail, at 900 AFFL, prefinished PVC	Equal to Acrovyn
DWWH-005	WINDOW	desirable

Fittings, Furniture and Equipment (FF&E) Items

AusHFG code	Description	Group	Qty	Comment
DWWD-006	BLIND: venetian	3	1	to windows if provided
FQBS-018	CHAIR: office, ergonomic	3	1	to bench

AHHA
aservaludan health infrastructure allinose
contractors countries no ot other major industries

Page: 1 Print Date: 20/03/2017







Room Name

Set-up Room

Room Number SETUP-8

AusHFG code	Description	Group	Qty	Comment
FQGE-005	CLOCK: analogue, battery operated	3	1	
ITNE-007	COMPUTER: desktop, with display screen	3	1	
FIJO-152	CUPBOARD: wall mount, shelf unit, adj shelves	1	1	over desk, optional
FQDW-037	DESK: adj height, 1500W x 750D x 750H nom.	3	1	
FQSM-007	PEDESTAL: mobile, drawer unit, 660H	3	1	under desk
FQSM-015	SHELVING: stainless steel wire mesh, mobile	3	2	
ITNE-049	TELEPHONE: handset, desktop	3	1	to desk
MMGE-123	TROLLEY: instrument	3	1	
FIBM-018	WHITEBOARD: fixed	2	1	900 x 900, optional

Engineering Services

AusHFG code	Description	Group	Qty	Comment
ELGP-208	GPO: double, wall mounted	1	2	
ITIN-026	OUTLET: data, double RJ45, wall mounted	1	1	



Page: 2 Print Date: 20/03/2017